


# IMPACT OF THE FULL SYSTEM CHEMICAL DECONTAMINATION ON THE JOSÉ CABRERA NPP DECOMMISSIONING


*BRUSSELS\_ JUNE 2016*





## RCS

- Reactor Vessel & Internals
- Steam Generator
- Reactor Coolant Pump
- Pressurizer
- System piping




## Auxiliary systems

- Residual Heat Removal System (RHR)
- Chemical & Volume Control System (CVC)



## Combination of Two Processes



Phase 1: 3 Nitrox cycles + 2 DfD cycles

Phase 2: 1 DfD cycle

Phase 3: 4 DfD cycle (only CVC and RHR systems)

## MAIN GOALS

- To reduce the levels of radiation and contamination
- To facilitate the dismantling of the plant's large components
- To reduce individual and collective doses

Quantity / DF	Final Results
Total Activity (Ci)	802
Co60 Activity (Ci)	714
Metal Removed (kg)	234
Decon Factor (DF)	
SG Tube Bundle	12
Auxiliary Systems	33
Primary System	8
Pressurizer	50
Resins (m <sup>3</sup> )	13

## P-mSv / FINAL DECONTAMINATION PROCESS


Task	P-mSv
Plant Modifications	23
Maintenance & Inspections	11
Decontamination process	25 (21%)
Spent resins conditioning	60 (50%)
TOTAL	119

- Decommissioning estimated dose


6416

119 (1,9%)


- Final decontamination collective dose



**22  
reference  
points**







Final\* Collective  
dose: 1.3

Anticipated\* dose  
with decon: 1.4

Anticipated\* dose  
without decon: 4.1

**P-Sv**

Reduction:



**2.8 Sv-p**

**68 %**





\* In tasks affected by  
decontamination

# Conclusions


- ✓ The DF attained exceeded those expected for the Pressurizer and the Auxiliary Systems
- ✓ DF's were lower than expected for the SG due to the presence of plugged tubes (8%)
- ✓ The overall DF's were on the order of other similar decontamination projects
- ✓ The personnel dose for the dismantling was significantly reduced
- ✓ Radiological risks, including the risk of airborne radioactivity, were reduced
- ✓ Very good visibility for the vessel and internals segmentation works, increasing productivity



- **75% Project progress**
- **Full RCS and auxiliary systems segmented**
- **Removing Biological Shielding**
- **Removing Cavity and Spent Fuel Pool contaminated walls**
- **Expected Completion Date: 31st December 2018**




## Collective dose




## Collective dose per task, updated at 31st March 2016

<i>Qum.</i>		WORK GROUPS	<i>Acumulado</i>	
142,77	<i>RV internals</i>	Plant Modifications	144,11	6,7%
234,35	<i>Reactor vessel</i>	Maintenance & surveying	347,03	16,1%
329,71	<i>Steam generator</i>	<i>Large components</i>	846,00	39,1%
16,64	<i>Pressurizer</i>	Decontamination in situ (components)	29,03	1,3%
122,54	<i>Pump &amp; loop pipes</i>	Spent fuel pool conditioning & decon	95,79	4,4%
846,00	<i>total</i>	Dismantling in Containment building	177,67	8,2%
		Dismantling in other buildings	180,73	8,4%
		Biological shielding removal	18,71	0,9%
		Contaminated concrete removal	120,34	5,6%
		Surfaces decontamination	20,81	1,0%
		Decontamination workshop	0,25	0,0%
		Rad Waste managing	181,61	8,4%
		<i>total</i>	<i>2162,07</i>	

*Figures in mSv-p*

**Collective dose per task, updated at 31st March 2016****COLLECTIVE DOSE PER TASK**

## Highest individual dose, updated at 31st March 2016







GOBIERNO  
DE ESPAÑA

MINISTERIO  
DE INDUSTRIA, ENERGÍA  
Y TURISMO

