

US NRC ALARA Findings and Observations

January 13, 2015


Manuel Jimenez
Health Physicist
NRC Division of Risk Assessment
Radiation Protection and Consequences Branch





Collective Dose 1994 – 2013

(Preliminary NUREG-0713)








Average Number of Individuals with Measurable Dose per Reactor 1994 – 2013


(Preliminary NUREG-0713)







Average Measurable Dose per Individual 1994 – 2013 (Preliminary NUREG-0713)



^{*} Not adjusted for transient workers.





Three-Year Dose Average 2011–2013

(Preliminary NUREG-0713)

For BWRs

- 1st Quartile: 57.725 85.497 person-rem
- 2nd Quartile: 96.397 127.064 person-rem
- 3rd Quartile: 130,650 158,144 person-rem
- 4th Quartile: 158.250 241.675 person-rem

For PWRs

- 1st Quartile: 17.321 39.651 person-rem
- 2nd Quartile: 39.663 45.306 person-rem
- 3rd Quartile: 46.481 53.181 person-rem
- 4th Quartile: 58.334 121.128 person-rem



Inspection Procedure (IP): Radiation Safety – Public and Occupational

- IP 71124 (Eight Attachments)
- Attachment No. 71124.02, "Occupational ALARA Planning and Controls"
- Assess performance with respect to maintaining radiation exposures ALARA
 - Review ALARA work plans and verify dose estimates
 - Review performance of work activities (Actual vs Estimate)
 - Review radiation worker performance



Attachment No. 71124.02

- Determine plant's quartile for three-year dose average
- Schedule inspection hours (biennial)
 - Top quartile
 44 inspection hours
 - Mid quartiles
 54 inspection hours
 - Lowest quartile
 64 inspection hours
- Adjust hours as appropriate based on the plant source term and overall ALARA effectiveness



ALARA compliance with regulations

- ALARA "regulatory" compliance is based on whether licensees have adequate procedures to track and reduce collective dose
- Compliance is not based on whether individual doses are the absolute minimum, or use of all possible ALARA methods



Program Assessment

- Effectiveness of ALARA assessed on a work activity-by-work activity basis
- Actual dose outcome of a work activity is compared to the planned, intended dose for that work activity
- Large Differences in Actual vs Estimate may be an indication of a potential weakness or failure



Collective Dose Issue Screening

(IMC 0308 Appendix C)

Minor Issues

- The actual dose ≤ 50% above the planned, intended collective dose
- The actual dose > 50% above the planned, intended collective dose and the actual dose < 5 person-rem


More-than-Minor Issues

- The actual dose > 5 person-rem and the actual dose
 > 50% above the planned, intended collective dose
 - Failure to establish, maintain or implement procedures or engineering controls



Significance Determination Process

(IMC 0609 Appendix C)





Last 24 Months ALARA Findings

- 1. Reactor Coolant Pump (RCP) Activities ML14314A052
- 2. Control Rod Drive Mechanism (CRDM) Repairs ML14127A543
- 3. (Two Jobs) In-Service Inspections (ISI) Examinations and Snubber Inspections ML14041A007
- 4. ISI Examinations ML14045A089
- 5. Reactor Re-Assembly and Cavity Decon ML13310A647
- 6. Chemical Volume Control System (CVCS) Piping Modification ML13221A584
- 7. Spent Fuel Pool (SPF) Cooling Heat Exchanger Replacement ML13042A373



Causes

Job Planning

- Inadequate work scope
- Inadequate walkdowns
- Underestimation of time to perform job

Job Execution

- Rework
- Poor coordination of shielding installation
- Lack of coordination of support groups



Questions and Discussion

