



#### **Overview**

- Initiating events
- Requirements
- Procedure
- Results
- Outlook
- Conclusions



#### Initial event 1: Hot workshop intake air chiller drain



#### Initial event 2: Cold condensate storage tank vent

- Cold condensate containing I-131 after fuel failures
- Changes in water level push lodineair out of tank vents
- Contamination found outside RCA



#### A review of the RCA boundary ?

- HSK = Hauptabteilung für Sicherheit der Kernanlagen = Swiss regulator
- HSK-requirement: "A comprehensive review of the entire RCA boundary has to be performed"
- Guideline requirement: "Radioactive effluents may cross the RCA-boundary only on licensed pathways, controlled and compared to release limits"
  - Licensed pathways: Ventilation to stack, Radwaste discharge
  - Controlled: Any instrument reading [cps]
  - ☆ Compared to release limits: qualified sampling and counting reading [Bq]

#### **Gentlemans Agreement with HSK**

- Identified unlicensed pathways with existing release: reportable event
  - Existing release = contaminated pathway
  - Amount of release doesn't matter. Everything above background.
- Identified unlicensed pathways without release: general amnesty
  - Aim: No penalty for serious review

#### Consequences

- Review of the Hot Workshop took 2 years, about 0.3 man-year
- Involved: Radiation protection, ventilation engineer, radwaste engineer, civil engineer
- A radiation protection engineer was hired to manage the further project
- Review building by building
- Reporting to HSK every 6 months

# Interfaces between radioactive and non-radioactive systems

- WANO-Peer-Review 2005: "Some interface do not have isolation provisions to prevent contamination of the non-radioactive system"
- What is an "isolation provision" to provide a "safe" interface?
- A safe interface consists of two barriers (two-barrier-concept):
  - A Check-valve
  - ☆ A reliable pressure difference
  - Integrity of component (like a tight heat exchanger tube)
  - Radiation monitor in non-radioactive system (Only under certain circumstances)

## Additional tasks:

![](_page_8_Figure_1.jpeg)

![](_page_8_Picture_2.jpeg)

## **Review of RCA - Penetrations: Procedure**

- 1. Search and identification of penetrations through RCA boundary
  - 1) Walk Downs in the field
  - 2) Discussions with RP/Engineering-staff to gather operational experience
- 2. Verify the the identified penetrations in the as-built documentation
- 3. Assessment of the findings
- 4. Suggest technical solutions to improve unacceptable situations
- 5. Report to Plant Safety Committee and HSK
- 6. Follow up of plant modifications

![](_page_9_Picture_9.jpeg)

## **Penetrations: Turbine building findings**

- A total of 205 penetrations were evaluated
- Rainwater drain lines crossing the RCA

![](_page_10_Picture_3.jpeg)

![](_page_10_Picture_4.jpeg)

• Vertical penetration through turbine building foundation

![](_page_11_Picture_1.jpeg)

![](_page_11_Picture_2.jpeg)

 Emergency ventilation exhaust

## **Penetrations: Reactor Auxiliary Building findings**

- Reactor Aux Building = RCA
- 2 ventilation concepts:
  - o **ECCS-rooms:** Ventilation to stack, qualified radiation monitors
  - Other rooms (hallways, diesels etc.):
    Ventilation to roof, no qualified radiation monitors)
- Ventilation to the environment without qualified radiation monitoring is a violation of RCArequirements per se

![](_page_12_Picture_6.jpeg)

![](_page_12_Picture_7.jpeg)

## **Penetrations: ECCS maintenance**

- Maintenance of ECCS-pumps in Aux-building hallway
  - Maintenance of a heavily contaminated
    component without proper ventilation flow stack
    has the risk of a real release via unlicensed
    pathway
- Temporary solution 2008 and 2009:
  - o Tent around maintenance location
  - o mobile HEPA-filters
  - Redirect ventilation flow from tent to ECCSrooms
- Final solution to be discussed

![](_page_13_Picture_8.jpeg)

![](_page_14_Figure_0.jpeg)

#### Penetrations: cold condensate storage building

![](_page_15_Picture_1.jpeg)

- New roof
- New ventilation
- New coating inside
- 2.5 million \$
- New part of the RCA

![](_page_15_Picture_7.jpeg)

![](_page_15_Picture_8.jpeg)

![](_page_15_Picture_9.jpeg)

![](_page_15_Picture_10.jpeg)

## Penetrations: miscellaneous findings

- Abandoned tube for electric cables in Radwaste building wall
- Open penetration through RCA-boundary

![](_page_16_Picture_3.jpeg)

![](_page_16_Picture_4.jpeg)

![](_page_16_Picture_5.jpeg)

![](_page_16_Picture_6.jpeg)

#### **Different types of penetrations**

![](_page_17_Figure_1.jpeg)

Folie 18

#### **Confusing?** Radwaste ventilation!

![](_page_18_Figure_1.jpeg)

![](_page_18_Picture_2.jpeg)

2009 ISOE ALARA Symposium/EPRI RP Conference

#### Interfaces: Findings in the turbine building

- Make up water outlets:
  - o Coupling fits to various types of hoses
  - o 1. Barrier = pressure difference
  - o 2. Barrier = non existant

![](_page_19_Picture_5.jpeg)

o Solution: Additional check valve for each outlet

![](_page_19_Picture_7.jpeg)

![](_page_19_Picture_8.jpeg)

- Underlying problem:
  - o Non radioactive systems, whose content is used inside and outside of RCA
  - o Examples: fire water, make up water, aux steam, compressed air, service air

#### **Interfaces: Findings in the Radwaste**

- Interface between cold condensate (radioactive) and make up water (nonradioactive):
  - o 1. barrier = non existant (similar system pressure)
  - o 2. barrier = non existant
- Valves are not considered to be a barrier, because their position can be "open" or "closed"

![](_page_20_Picture_5.jpeg)

#### **Interfaces: Special situations**

#### • Some parts of systems can't be protected with reasonable effort

- Drinking water system inside Hot Lab
- Water supply of Hot Laundry
- Parts of Auxiliary steam system

- Those parts of systems are "sacrificed"
  - Possible contamination is taken into account
  - Documentation for future modifications and decommissioning

![](_page_21_Picture_9.jpeg)

#### Work progress

#### • Review completed

- o Hot workshop
- o 10 kV-Switchyard
- o Cold condensate storage
- o Turbine building
- o Seismic gap between buildings
- o Steam tunnel
- o Off-gas building
- o Radwaste building
- o Containment

#### Review in progress

- o Auxiliary building
- o Fuel handling building
- o Waste storage building
- o Stack

![](_page_22_Figure_16.jpeg)

#### Conclusions

- Until now a workload of 3 man-years was generated
- Approx. 2/3 of the project is completed
- A dozen of plant modifications has been triggered
- The understanding in plant and systems design has improved among engineers and Radiation Protection
- A review like this will be part of the new plants licensing process
- KKL has become safer with regard to inadvertent release of radioactive material

![](_page_23_Picture_7.jpeg)

## **Questions?**